

CWL507-S-53 - SPEEDLINE TIMBER CEILING LINER SYSTEM

Type & Ref: --
Version V1(24/10/23) --

SPEEDLINE Reference: CWL507-S-53^(Timb)

Performance Overview:

Fire Resistance (minutes): NA.
Sound Insulation: NA R_wdB
Insulation Required: NA.
Soffit Depth: 20 -175 mm Dependent on bracket type used (background to face of channel).
Structural Soffit: Existing Timber Joist.

Steel Framing Detail:

Perimeter Tracks: **SPEEDLINE SWL60** secured to perimeter of the room, in the centre of the profile at 600 mm maximum centres with suitable fixings.
Liner Section: Install row of **SPEEDLINE SWL507** Ceiling Liner Section at 400 mm or 450 mm centres. Fit Liner Section into Perimeter Track at edges.
Brackets: Fix brackets **AH185** (75 mm leg), **AH186** (125 mm leg) or **AH175** (175 mm leg), to the timber soffit at maximum 900 mm centres. Secure brackets to Ceiling Liner Section using **SPEEDLINE Wafer Head Drywall Screws**, one fixing to each side of bracket. Fold back excess bracket to provide flush finish for board lining.

Plasterboard linings:

Outer Layer: 12.5 mm Siniat GTEC dB Board attached to underside of framing at 230 mm maximum centres with **25 mm SPEEDLINE Drywall Screws**. The perimeter of the room and ends of boards to be fixed at 150 mm maximum centres.
Humid Areas: Replace with 12.5 mm Siniat GTEC Fire MR Board attached to framing at 230 mm maximum centres with **25 mm SPEEDLINE Drywall Screws**.

Finishes:

Acoustic Seal: Skim plaster or taped & jointed (MR Boards to be taped & jointed only).
At junctions between partitions and any other air paths, apply a continuous bead of **SPEEDLINE Intumescent Sealant**, to clean dust free surfaces. Please Note: **SPEEDLINE Intumescent Sealant** is NOT compatible with Lubrizol cPVC pipes.

Accessories:

General Notes: **Service Support Plate AH174** & 18 mm Plywood for all pattresses.
To be installed in accordance with SPEEDLINE recommendations and relevant British standards including BS 8000-0:2014 and BS 8000-8:2023.
This document should be read in conjunction with clauses specified in original contract documentation. Flanking details to be appropriate to current requirements.